and office floor construction.

Roof Pitch - Crickets - Curbs - Gutters:- Built up crickets to give pitch shown, screeded and troweled to give smooth finish.

Roof Slab Openings:- Provide hatch, ventilator, pipe, stair and other openings in roof, reinforced, etc., as called for.

Forms:- All forms to be constructed of dressed T. & G. Lumber.

Placing and Supporting Forms:- All forms to be securely braced, held, tied or otherwise fastened and held so as to keep them true and plumb, and prevent them sagging, bulging or deforming.

Forms - Wetting:- When form work is completed in hot weather, it is to be kept wet until the concrete is placed, in order to prevent cracking, warping and shrinking of the forms.

Concrete-Forms - Wetting:- All form work must be thoroughly wetted down before concrete is placed, and kept wet until concrete has set, in order to prevent cracking. As soon as the concrete has attained its permanent set, generally in twenty-four hours, the entire exposed surface is to be drenched with water, and kept in this condition for four days, so as to prevent too rapid drying and consequent surface cracking.